FRENCH ROCKS DISTRICT.

The 14th September 1891.

List of Excess Amount of Fees and Penalties refundable to the Presenters of Documents in the Sub-Registry Office of the French Rocks District for the month of May 1891-92.

Name of Sub-Registry Office.	Names of Presenters of Documents.	Date of Document.	Nature of Document.	Excess amount of Fees and Penalties refundable.			Grounds for the Refund.	Date before which the application for refund should be made by the party entitled to it.	Remarks.
1	2	3	4	5			6	7	8
				Rs.	A.	P.			
Nagamangala.	Kapanigauda and Marigauda of Machanayakanahalli.	14th August 1890	Sale deed for Rs. eighteen.	*0	8	0	Executants did not present themselves within the time prescribed by the Registration Act, &c. Hence registration refused. Claimants did not take proper steps required by the Act within due time. Hence the refund.	30th October 1891.	

*Eight annas only.

D. DEVARAJ ARS,
Registrar.

TUMKUR DIVISION.

ADVERTISEMENT.

The 15th September 1891.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 15th October 1891, for restoring the Magodi Tank, R. No. 29 of Sira Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1893.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Magodi Tank, R. No. 29 of Sira Taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of Work.	Per.	Quantity.	Rate.	Cost.
Bund—				
Earthwork	C. Yd.	69,934		
New stone work	Do	4,593		
Old stone work and new stone work to be reset ..	Do	1,548		
Grade stones	No.	17		
B. M. stones	Do	2		
Sluice—				
Repairs	L. S.	..		50
Left Waste Weir—				
Excavation	Do	..		5
Brick in chunam	C. Ft.	942		
Chunam plastering	Sq.	12 57		
Concrete	C. Ft.	368		
Covering slabs 6" thick	S. Ft.	1,079		
New stone work	C. Yd.	301		
Old stone work	Do	23		
Packing jelly to old apron	L. S.	..		50
Right Waste Weir—				
Excavation	L. S.	..		10
Brick in chunam	C. Ft.	5,969		
Chunam plastering	Sq.	24·52		
Concrete	C. Ft.	906		
Covering slabs 6" thick	S. Ft.	2,619		
New stone work	C. Yd.	188		
Old stone work	Do	58		
Packing jelly to old apron	L. S.	..		100
Distribution—				
Building a masonry wall to the present waddu across right kodi nala and excavating irrigation channel for 1 mile	L S.	..		1,000

C. T. Dalal,
Executive Engineer.

SPECIAL IMPROVEMENTS DIVISION.

Advertisement.

The 14th September 1891.

Tenders are hereby invited for constructing range of bazaars from Sivarampet Bridge to Jagan Mohan Palace Road. An approximate estimate of quantities is given below. These quantities are not guaranteed.

2. The plans, estimates, schedule of rates and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A. M. and 5 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Sanitary Engineer. These forms should be filled in, signed by the contractor and forwarded in sealed covers to the Sanitary Engineer before the 30th September 1891.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 100 as earnest money.

6. Within 8 days of the acceptance of the tender, the contractor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor, whose tender has been accepted, will be posted on the notice board in the Sanitary Engineer's Office in due course. No enquiries respecting the acceptance or rej-